


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 12 Twp. 24 Rge. (E) 13(W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Murfin Drilling Co.
Lease Name Zeigler Well No. 1
Office Address 617 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-6 19 58
Application for plugging filed 5-6 19 58
Application for plugging approved 5-6 19 58
Plugging commenced 5-6 19 58
Plugging completed 5-6 19 58
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot, St. John, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4100 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 230' mixed 20 sacks displaced through drill pipe. Set top plug at 40' mixed 10 sacks.

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1958

6-6-58

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company
Address 617 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WR Murfin

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 58

My commission expires June 14, 1961

Phyllis Brown
Phyllis Brown

Notary Public.

PLUGGING
FILE SEC 12 T 24 R 13W
BOOK PAGE 99 LINE 37

15-185-00490-0000

WELL LOG

COMPANY Murfin Drilling Co.

SEC. 12 T. 24 R. 13

FARM Zeigler

NO. 1

LOC. SE SE SE

TOTAL DEPTH 4100


COMM. 4-21-58

COMP. 5-6-58

SHOT OR TREATED

CONTRACTOR Murfin Drilling Co.

ISSUED

COUNTY Stafford
KANSAS

CASING

20	10
15	8 5/8" @ 255' w/ 250 SXS.
12	6
13	5

ELEVATION 1894 DF 1896 RB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

TOPS:

145	Sand - Gravel	Heebner	3340'
255	Shale - Shells	Douglas	3374
730	Red Shale - Shells	Brown Lime	3481
757	Anhydrite	Lansing	3511
1230	Shale - Shells	Base Kansas City	3747
1355	Salt - Shale - Shells	Conglomerate	3822
1625	Shale - Shells	Viola	3879
1925	Lime - Shale	Simpson	4011
2050	Lime	Arbuckle	4069
2180	Lime - Shale	RTD	4100
2295	Lime		
2360	Lime - Shale		
2800	Shale - Lime		
3185	Lime - Shale		
3515	Shale - Lime		
3845	Lime		
3880	Shale		
4010	Lime		
4015	Sand		
4070	Shale - Lime		
4100	Arb.		

6-6-58

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 12 T. 24 R. 13W

BOOK PAGE 99 LINE 37

State of KansasCounty of Sedgwick

SS:

I, W. R. Murfin of the Murfin Drilling Companyupon oath state that the above and foregoing is a true and correct copy of the log of the Zeigler # 1 well.Subscribed and sworn to before me this 3rd day of June 19 58.My Commission Expires: June 14, 1961Phyllis Brown
Phyllis Brown NOTARY PUBLIC