

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 12 Twp. 24S Rge. 13 (X) W (W)

Location as "NE/CNW/SW" or footage from lines NW SW NW

Lease Owner: Graybol Contracting Corp. & L. B. Smith

Lease Name: Garner Well No. one

Office Address: 523 Petroleum Building

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed May 22, 19 53

Application for plugging filed May 22, 19 53

Application for plugging approved May 22, 19 53

Plugging commenced May 22, 19 53

Plugging completed May 22, 19 53

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4067 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 235'. Set plug with hulls above and below and ran 20 sacks of cement on top of plug. Filled with heavy mud to 40'. Set plug #2 with hulls above and below and filled hole with 10 sacks cement.

COMMISSION
JUN 1 1953
CONSERVATION DIVISION
Wichita, Kansas

6-1-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

523 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 19 53

[Signature] Notary Public.

My commission expires My Commission Expires Oct. 31, 1955

PLUGGING
FILE SEC 12 T 24 R 13W
BOOK PAGE 103 LINE 19

GRAYBOL CONTRACTING CORPORATION & L. B. SMITH
 #1 Garner NW SW NW Section 12-24 S- 13 W
 Stafford County, Kansas

Commenced: 5-7-53
 Completed: 5-22-53
 Total Depth: 4067'

Elevation: 1902' R.B.
 Initial Prod: Dry & Abandoned
 Contractor: Graybol
 Tools: Rotary

CASING RECORD

Run 242' 8 5/8" Surface Casing cemented with 175 sacks cement
Left in Hole 242' 8 5/8" Casing

STRATA	DEPTH	FORMATION TOPS	ROTARY BUSHING
Sand & Gravel	160	Topoka Lime	3024 (-1122)
Red Rock - Shale & Shells	242	Heebner Shale	3354 (-1452)
Shale & Shells	280	Toronto Lime	3379 (-1477)
Red Bed	740	Douglas Shale	3390 (-1488)
Anhydrite	765	Brown Lime	3494 (-1592)
Shale & Shells	1370	Lansing	3521 (-1619)
Lime & Shale	1730	Conglomerate	3831 (-1929)
Sandy Lime & Shale	1790	Viola Chert	3846 (-1944)
Lime & Shale	1840	Simpson	3968 (-2066)
Sandy Lime & Shale	2110	Arbuckle	4035 (-2133)
Lime & Shale	2165	Total Depth	4067 (-2165)
Shale	2240		
Lime & Shale	2855	Drill Stem Test #1 @ 3544-99'	
Shale	2880	Open 1 hour. Recovered 90' of mud with few specks oil. 810# B.H.P.	
Lime & Shale	3024		
Lime - Streaks of Shale	3354	Drill Stem Test #2 @ 3850-88'	
Black Shale	3359	Open 20 minutes. Recovered 10' mud. No.B.H.P.	
Tan Lime	3363		
Red & Gray Shale	3379		
White Lime	3390	Drill Stem Test #3 @ 3970-4002'	
Red & Green-gray Shale	3494	Open 50 minutes. Recovered 20' mud with specks of dead oil & 60' watery mud. 170# B.H.P.	
Brown Lime	3501		
Gray Shale	3521		
Lime - Streaks of Shale	3767		
Shale & Lime	3831		
Conglomerate	3846		
White & Cream Chert - Shale	3948		
Dolomitic Lime - Lime & Shale	3968		
Dolomite	3998		
Green Shale - Sandy Shale &	4035		
Sand			
Tan Finely Crystalline Dolomite	4067		
Total Depth	4067		

RECEIVED
 STATE COMMISSION
 DIVISION
 Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

GRAYBOL CONTRACTING CORPORATION

By A. N. Ward
 A. N. Ward

STATE OF KANSAS)
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 28 day of May, 1953.

My Commission Expires Oct. 31, 1955.

PLUGGING
 FILE REC 12 T 24 R 13W
 BOOK PAGE 103 LINE 19

Charles J. Roberts
 Notary Public