


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

36 - 30 - 8W

Kingman County, Sec 36 Twp 30 Rge. 8 (W)

Location as "NE/CNWSW" or footage from lines NE 1/4 NE 1/4  
Lease Owner Augrove Petroleum Corporation of WI  
Lease Name OWNER Well No. 1  
Office Address 201 Union Center Bldg. - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 31 1959  
Application for plugging filed October 31 1959  
Application for plugging approved October 31 1959  
Plugging commenced October 31 1959  
Plugging completed October 31 1959  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Orad Hessel - Gretty Prairie, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4110 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	201'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole with 30 sacks of cement on bottom heavy mud to 200', set plug with 1/4 sack of bulite and 10 sacks of cement through drill pipe heavy mud to 100', set plug of 1/4 sacks of bulite and 10 sacks dry cement bridged rat-hole with bulite and 5 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 13 1962  
7-13-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ayikawa Drilling Company  
Address 212 1st Nat'l Bank Bldg. - Wichita, Kansas

STATE OF KANSAS COUNTY OF Sedgewick ss.  
Paul W. Hesse, Agent (employee of owner), or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse  
212 1st Nat'l Bank Bldg. - Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 10th day of November, 1959  
Duane Jessup  
DUANE JESSUP Notary Public.

My Commission expires December 11, 1961

15-095-00338-0000

DAUER NO. 1

Casing Records  
6 5/8" - 201'

Company: Musgrove Petroleum Corporation  
Contractor: Aylward Drilling Company  
Commenced: October 10, 1959  
Completed: October 31, 1959

Location: NE NW NW  
Sec. 36-30-8W  
Kingman County  
Elevation: 160' K.B.

	From	To	Remarks
Clay & Sand	0	70	Set 6 5/8" surface pipe @ 201'
Sand & Red Rock	70	120	w/175' max cement.
Red Rock	120	242	
Red Rock, Gyp & Clay	242	700	Geological Tops:
Blue Shale & Shells	700	1030	Heatnor 3318
Anhydrite	1030	1065	Douglas 3559
Shale, Shells & Salt	1065	1550	Lening 3514
Line & Shale	1550	1545	Mississippi 4303
Line	1545	2210	Total Depth 4147
Line & Shale	2210	2415	
Shale & Line	2415	2625	DST 4327-40 Open 1 hr. Str. bl.
Line & Shale	2625	2765	Gas to surf./28", too small to meas.
Shale & Line	2765	3105	Rec. 30" sl. GCM w/few specs oil.
Sand	3105	3305	IBHP 1875'/20" - FBHP 665'/20"
Shale & Line	3305	3585	FP 07/20" - 07/20"
Line & Shale	3585	3695	
Sand	3695	3515	DST 4340-70 Open 1 hr. 1/4" bl. dec.
Line	3515	3735	to very wk. Rec. 20" mud.
Line & Shale	3735	3860	IBHP 60'/20" - FBHP 0'/20"
Line	3860	4110	FP 07-07/20"
Line & Shale	4110	4200	
Shale & Line	4200	4375	DST 4368-85 Open 1 hr. Wk. stcy bl.
Chert	4375	4435	Rec. 55" sl. GCM w/few specs oil.
Cherty Line	4435	4448 T.D.	IBHP 200'/20" - FBHP 00'/20"

DST 4383-4400. Open 1 hr. Str. bl.  
Rec. 5300' gas in pipe, 100' hvy oil  
& GCM, 90" sl. oily muddy wtr.  
IBHP 1575'/20" - FBHP 1110'/20"  
FP 70'/20" - 115'/20"

D.S.A.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1962  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles D. Williams

Subscribed and sworn to before me this 10th day of November 1959

Deane Jessup  
Notary Public

My commission expires December 11, 1961