

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21918-0000

SF4, Sec. 30, T24 S, R 12 W/0

1980 feet from ~~W~~/S section line

1980 feet from ~~W~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Lease Name Doris Jenkins Well # 1

Operator: Stearling Drilling Co.

County Stafford

Name & Address P.O. Box 129
Stearling, Kansas 67579

Well Total Depth 4170 feet 135.52

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 310

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Stearling Drilling Co. License Number 5142

Address P.O. Box 129 Stearling, Kansas 67579

Company to plug at: Hour: 1:00 AM Day: 14 Month: 1 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Von Thompson

(company name) Stearling Drilling Co. (phone) _____

were: 1st plug @ 4100' w/ 50 lb cement.

2nd plug @ 750' w/ 50 lb cement.

3rd plug @ 360' w/ 50 lb cement.

4th plug @ 40' to 0' on solid bridge w/ 10 lb cement.

Circulate 15 lb cement in rat hole & plug water well w/ 5 lb cement.

Signed Paul A. Luttie
(TECHNICIAN)

Plugging Operations' attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:30 AM Day: 14 Month: 1 Year: 1984

ACTUAL PLUGGING REPORT 1st plug filled hole w/ heavy mud & spotted 50 lb cement.

through drill pipe @ 4100'. 2nd plug up hole full of heavy mud spotted @ 750' w/ 50 lb cement through drill pipe. 3rd plug up hole full of heavy mud spotted 50 lb cement through drill pipe to 360'. 4th plug filled hole to 40' w/ heavy mud dumped 2 1/2 bbls in hole & pushed rubber plug to 40' on solid bridge & spotted 10 lb cement filling hole to 0'. Circulated 15 lb cement in rat hole through drill pipe. Then plugged water well with 5 lb cement. Wellbore cementing accomplished. The cementing w/ 60/40 gogg w/ 2% gell.

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1984

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1-20-84

INV. NO. 92141W

Signed Paul A. Luttie
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82