

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185 -21,975-0000

SE SW SW , Sec. 19 , T 24 S, R 12 (W/E)

330 feet from ~~W/S~~ section line

990 feet from W~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020

Lease Name Curtis Well # ~~1-29~~ 1-19

Operator: Rine Exploration Company
Name & 300 West Douglas, Suite 645
Address Wichita, KS 67202

County Stafford

Well Total Depth 4170 feet 135.53

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor J. W. Drilling License Number 5137

Address 200 East First, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 12:05 pm Day: 26 Month: April Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Bill Roach

(company name) J. W. Drilling (phone) 316-278-2367

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4130' with 40 sx cement

2nd plug at 740' with 50 sx cement

3rd plug at 400' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' --- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement

Signed *J. A. Mef*
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 3:00 pm Day: 26 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4130' with 40 sx cement, 2nd plug at 740' with

50 sx cement, 3rd plug at 400' with 50 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 40' --- cement to surface with 10 sx cement, 6th plug to circulate rathole

with 15 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied

RECEIVED
STATE CORPORATION COMMISSION
MAY 03 1984
CONSERVATION DIVISION
Wich.

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

Signed *J. A. Mef*
(TECHNICIAN)

INVOICED

DATE 5-7-84

INV. NO. 1393