

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20391-00-01

Spot: NESWNE

Sec/Twnshp/Rge: 1-24S-42W

3630 feet from S Section Line, 1650 feet from E Section Line

Lease/Unit Name: TATE

Well Number: 1-1

County: HAMILTON

Total Vertical Depth: 2307 feet

Operator License No.: 8671

Op Name: TATE EXPLORATION

Address: PO BOX 69 101 N. MAIN  
LAKIN, KS 67860

Conductor Pipe: Size

feet:

374.98

Surface Casing: Size 8.625

feet: 367

WITH 240 SX CMT

Production: Size 4.5

feet: 2306

WITH 375 SX CMT

Liner: Size

feet:

Well Type: SWD

UTC Docket No: D22362.0

Date/Time to Plug: 03/20/2002 10:00 AM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CMT CIRCULATED TO SURFACE. PUMP 400# HULLS & 25 SX CMT & GEL TO 100'. PUMP CMT FROM 1000' TO 0'.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 03/20/2002 11:00 AM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2297'. PERFS AT 2282-88'. 4 1/2" CASING CEMENTED TO SURFACE. PUMPED DOWN 4 1/2" CASING 100# HULLS, 20 SX CMT, MUD SPACER 14.7 BBL, 75 SX CMT. CMT FROM 0-1050'. MAXIMUM PRESSURE 1300#. SHUT IN PRESSURE 1000'. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 11 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 700#.

RECEIVED

APR 21 2002

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed




(TECHNICIAN)

INVOICED MAR 28 2002

DATE 4-23-02

NO. 2002061691



FORM C-2/3

