

To: 120711
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-29 API NUMBER 15- 075-20,493 - 0000 207
SW SW SW, SEC. 3, T. 24 S, R. 43 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30519

Operator: Sinclair Oil Corporation

Name:

Address 1625 Broadway, Suite 800

Denver, CO 80202

330 feet from S section line

329 feet from WE section line

Lease Name Hadson-Low Well # 13-3

County Hamilton

Well Total Depth 5500 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 990

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 30606

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 29 Month: 4 Year: 19 92

Plugging proposal received from Donald Collins

(company name) Sinclair Oil Corp. (phone) 303-592-5345

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1710-40'

1st plug at 1740' with 50 sx cement, 2nd plug at 1020' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8 p.m. Day: 29 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1740' with 50 sx cement,

2nd plug at 1020' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.

(If additional description is necessary, use BACK of this form.)

INVOICED
(XXX) did not observe this plugging.

DATE 6-5-92

INV. NO. 35422

Signed

(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1992

CONSERVATION DIVISION
Wichita, Kansas

