

1 120486

10-10

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,138-0000

TECHNICIAN'S PLUGGING REPORT

App. SE SE NE, SEC. 16, T 24 S, R 17 W/E

App. 2970 feet from S section line

App. 330 feet from E section line

Operator License # 5056

Lease Name Cross Well # 1-16

Operator: F.G. Holl Company

County Edwards 144.30

Name & Address P.O. Box 780167

Well Total Depth 4440 feet

Wichita, KS 67278

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 10 Month: 10 Year: 19 90

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4439' w/125 sx cement, PBTD 4375', Perfs at 4350-62, 4382-84'

1st plug pump 1 sx hulls and 20 sx cement,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2 p.m. Day: 10 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 100 lbs. hulls, 50 sx cement to 3685',

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 150 lbs. hulls and 125 sx cement.

Pumping pressure 0-350 psi and shut in 20 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2400' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 23 1990

INV. NO. 29695

OCT 17 1990

CONSERVATION DIVISION Wichita, Kansas

Signed [Signature] (TECHNICIAN)