

1 120237

MAR 29 1989
API NUMBER 15-

20370
047-20,376-0000

304 R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2 W/2 NW/4, SEC. 19, T 24 S, R. 17 W/K
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3960 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Cross Well # 1-19

Operator: F.G. Holl Company

County Edwards 147.91

Name & Address P.O. Box 780167

Well Total Depth 4551 feet

Wichita, KS 67207

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 29 Month: 3 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4550' PBTD 4515' Perfs at 4432-36'

1st plug sand back to 4380' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 29 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4380' and dumped 4 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement

Pumping pressure 0-400 psi and shut in 300 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2474' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form)

APR - 3 1989
4-3-89

INVOICED observe this plugging.

Signed Duan Rankin (TECHNICIAN)

DATE 4-19-89

INV. NO. 24343