

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20305-00-00  
Spot: SENWNWSE Sec/Twnshp/Rge: 9-24S-17W  
390 feet from N Section Line, 387 feet from W Section Line  
Lease/Unit Name: ENLOW Well Number: H-1  
County: EDWARDS Total Vertical Depth: 4460 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 6427 EAST KELLOGG  
WICHITA, KS 67207

Conductor Pipe: Size feet: 9144.95  
Surface Casing: Size 8.625 feet: 254 WITH 225 SX CMT  
Production: Size 4.5 feet: 4457 WITH 125 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/07/2002 2:10 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4300' & 4 SX CMT. 1ST PLUG AT 1150' WITH 10 SXGEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/07/2002 3:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PERFS AT 4376-4380'. SAND TO 4300' WITH 4 SX CMT. 1ST PLUG PULL TO 1150'. SPOT 10 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 300' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT.

RECEIVED

JUN 12 2002

KCC WICHITA


6-12-02

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2280' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

INVOICED JUN 10 2002

DATE

6-13-02

INV. NO.

2002061944

Form CR-2/3