

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21371-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 9-24S-17W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: ENLOW H Well Number: 3
County: EDWARDS Total Vertical Depth: 4500 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 6427 EAST KELLOGG
WICHITA, KS 67207

Conductor Pipe: Size feet: 8 1/4 25
Surface Casing: Size 8.625 feet: 314 WITH 225 SX CMT
Production: Size 4.5 feet: 4496 WITH 225 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/06/2002 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4300' WITH 5 SX CMT. 1ST PLUG AT 1150' WITH 50 SX CMT. 2ND PLUG AT 350' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/06/2002 12:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:
PBTD 4470'. PERFS AT 4342-4352'. SAND TO 4286' & 4 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1150' WITH 5 SX GEL - 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
JUN 10 2002
KCC WICHITA
6-10-02

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2600' OF 4 1/2" CASING.
Plugged through: CSG

District: 01 Signed Richard W. Lacey (TECHNICIAN)
INVOICED JUN 07 2002
DATE 6-13-02
INV. NO. 2002061944