

To: **1 051854** *10-23*
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,402-6000
NW NW NE, SEC. 1, 7 24 S, R 17 W/X
330 feet from N & section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588
Operator: Woodman-Tannitti Oil Company
Name:
Address P.O. Box 308
Great Bend, KS 67530-0308

Lease Name Henning Well # 2
County Edwards *143.00*
Well Total Depth 4400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 223

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241
Address P.O. Box 819, Russell, KS 67665-0819

Company to plug at: Hour: 3 a.m. Day: 23 Month: 10 Year: 19 94

Plugging proposal received from Bill Owen
(company name) Emphasis Oil Operations (phone) 913-483-3518

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1090-1116'
1st plug at 1110' with 50 sx cement, 2nd plug at 250' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 7 a.m. Day: 23 Month: 10 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1110' with 50 sx cement,
2nd plug at 250' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)
10-25-94
observe this plugging.

INVOICED
DATE 11-9-94
INV. NO. 41619

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1994
Signed Richard Lacey
(TECHNICIAN)