

1 030810

6-5-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,282 -0080

W/2 W/2 NW, SEC. 1, T 24 S, R 17 W/E
3960 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3295

Lease Name Charities Well # 1-1

Operator: David W. Clothier
Name & Address 225 North Market, Suite 300
Wichita, KS 67202

County Edwards 145.93

Well Total Depth 4490 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 5 Month: 6 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4479' Perfs at 4338-4344'

1st plug sand back to 4280' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cem, release 8 5/8" wiper plug and pump 150

sx cement.

Plugging Proposal Received by Paul Luthi and Steve Durrant.
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:40 p.m. Day: 5 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 4 sx cement on top of sand
through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, released wiper plug and

pumped 150 sx cement.

JUN 9 1987 6-9-87

Maximum pressure 600 psi and shut in 150 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3101' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

Signed Steve Durrant
(TECHNICIAN)

DATE 6-9-87

INV. NO. 17196