

To: 1 090821  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

6-11

API NUMBER 15- 047-21,421-0000  
C NE NE, SEC. 1, T 24 S, R 17 W/X  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3456  
Operator: AFG Energy Inc.  
Name:  
Address P.O. Box 458  
Hays, KS 67601

Lease Name Henning Well # 3  
County Edwards 143.00  
Well Total Depth 4400 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A  X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Discovery Drilling License Number 31548  
Address P.O. Box 763, Hays, KS 67601

Company to plug at: Hour: 8 p.m. Day: 11 Month: -6 Year: 1997

Plugging proposal received from Tom Alm

(company name) Discovery Drilling (phone) 913-623-2920

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1106'  
1st plug at 1110' with 50 sx cement, 2nd plug at 330' with 50 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 10 p.m. Day: 11 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1110' with 50 sx cement,  
2nd plug at 330' with 50 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

6-13-97

RECEIVED  
KANSAS CORPORATION  
JUN 13 1997  
P. 2:52

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

I (operator) did not observe this plugging.

Signed \_\_\_\_\_ (TECHNICIAN)

**INVOICED**  
DATE 6-16-97  
INV. NO. 48349  
6-11