

To: 1 040267  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-20  
API NUMBER 15- 047-21,336-0000  
SE NE SE, SEC. 25, T 24 S, R 17 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Company  
Name &  
Address P.O. Box 780167  
Wichita, KS 67278-0167

1650 feet from S section line  
330 feet from E section line

Lease Name Stapleton "C" Well # 1-25  
County Edwards 147.88

Well Total Depth 4550 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sterling Drilling Company License Number 5142

Address P.O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 12:30 a.m. Day: 20 Month: 4 Year: 19 89

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2105'  
Anhydrite 1121-33'

1st plug at 1133' with 50 sx cement, 2nd plug at 570' with 50 sx cement,

3rd plug at 330' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:30 a.m. Day: 20 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1137' with 50 sx cement,

2nd plug at 570' with 40 sx cement,

3rd plug at 330' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

I (X) did not observe this plugging.

DATE 4-27-89

INV. NO. 2449.9

Signed Stephen J. Pfeifer  
(TECHNICIAN) SPJ

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1989  
CONSERVATION DIVISION  
WICHITA, KANSAS  
4-24-89