

1 120251

5-3

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,586-0000

SW NW, SEC. 1, T. 24 S, R. 14 W/E
2970 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9324

Lease Name Bookstore Well # 2-1

Operator: JFW, Inc.

County Stafford 137.48

Name & Address RR 1, Box 26

Well Total Depth 4230 feet

Plevna, KS 67568

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 419

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 West Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 3 Month: 5 Year: 19 89

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 820-830'

1st plug at Arbuckle with 30 sx cement, 2nd plug at 850' with 50 sx cement,

3rd plug at 450' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 3 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 4110' with 30 sx cement,

2nd plug at 850' with 50 sx cement,

3rd plug at 450' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

MAY 9 1989

5-9-89

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 5-10-89

Signed Duane Rankin (TECHNICIAN)

INV. NO. 24741

