

1 050191

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,167-0000

SW SE NW, SEC. 11, T 24 S, R 17

2310 feet from N~~W~~ section line

1650 feet from W~~E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Grizzelle Well # 2-11

Operator: F. G. Holl

County Edwards

Name & Address 6427 East Kellogg

Well Total Depth 4540 147.55 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Company License Number 5142

Address P. O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 4:30 am Day: 14 Month: April Year: 19 84

Plugging proposal received from Vaughn Thompson

(company name) Sterling (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1140' with 50 sx cement

2nd plug at 570' with 50 sx cement

3rd plug at 300' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement. Plug water well with 5 sx cement

Plugging Proposal Received by Richard W. Lacy (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 am Day: 14 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1140' with 50 sx cement, 2nd plug at 570' with 50

sx cement, 3rd plug at 300' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement. Plug water well with 5 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

(State and local) observe STATE CORPORATION COMMISSION

DATE 4-20-84

APR 20 1984

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 1190

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84