

1-120418

4-30

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,354 - 0000
C NE SW, SEC. 11, T 24 S, R 17 W/EX

TECHNICIAN'S PLUGGING REPORT

1980 feet from S section line
3300 feet from E section line

Operator License # 5056

Lease Name Enlow-Miller Well # 8-11

Operator: F.G. Holl Company
Name: _____
Address: P.O. Box 780167
Wichita, KS 67278-0167

County Edwards 149.37

Well Total Depth 4596 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A x

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Company License Number 5142

Address Sterling, KS

Company to plug at: Hour: 5 p.m. Day: 30 Month: 4 Year: 19 90

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1129-47'

1st plug at 1150' with 50 sx cement, 2nd plug at 600' with 50 sx cement,

3rd plug at 360' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 7 p.m. Day: 30 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1150' with 50 sx cement,

2nd plug at 600' with 50 sx cement,

3rd plug at 360' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION 5-8-90

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.
(If additional description is necessary, use BACK of this form.)

INVOICED
CONSERVATION DIVISION
Wichita, Kansas observe this plugging.

DATE 5-16-90

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 28156