

To: 1051341  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App.  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-9  
API NUMBER 19-047-20,611-0000  
SE SE NW, SEC. 12, T 24 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Company

Name: F.G. Holl Company

Address P.O. Box 780167

Wichita, KS 67207

3080 feet from S section line

2690 feet from E section line

Lease Name Brensing "B" Well # 2-12

County Edwards 143.00

Well Total Depth 4400 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 276.76

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:40 p.m. Day: 9 Month: 8 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-995-3171

were: 4 1/2" at 4396', PBT 4363', Perfs at 4315-23'

1st plug sand back to 4260' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:40 p.m. Day: 9 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4260' and dumped 4 sx cement on top of

sand through bailer, 8-14-90

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 350 psi and shut in 132 psi.

Witnessed by Steve Middleton.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2400' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

**INVOICED** (If applicable) observe this plugging.

DATE: AUG 23 1990

INV. NO. 29012

Signed Richard W. Leach  
(TECHNICIAN)