

10-20-87

1 061022

API NUMBER 15- 047-21,293 -0600

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION N/2 NE SW NW, SEC. 12, T 24 S, R 17 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3795 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Brensing "B" Well #8-12

Operator: F.G. Holl Company

County Edwards 143.33

Name & Address P.O. Box 780167

Well Total Depth 4410 feet

Wichita, KS 67278-0167

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sterling Drilling Company License Number 5142

Address Box 129, Sterling, KS 67579

Company to plug at: Hour: 2:45 p.m. Day: 20 Month: 10 Year: 19 87

Plugging proposal received from Von Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 570' with 50 sx cement,

3rd plug at 300' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:10 p.m. Day: 20 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1180' with 50 sx cement,

2nd plug at 330' with 50 sx cement, 10-22-87

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

OCT 22 1987

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-28-87

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 18687

10-20