

301 R

To: 1 120239
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

MAR 29 1989
API NUMBER 15-047-21,173-0000

SW SW SE, SEC. 12, T 24 S, R 17 W 1/4
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company
Name & Address: P.O. Box 780167
Wichita, KS 67207

Lease Name Schartz Well # 7-12
County Edwards 14199
Well Total Depth 4369 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 29 Month: 3 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4360' PBT 4311' Perfs at 4288-94'
1st plug sand back to 4238' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 p.m. Day: 29 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4238' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement
Pumping pressure 0-400 psi and shut in 250 psi.

4-3-89
RECEIVED
STATE CORPORATION COMMISSION

APR 5 1989

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2285' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

Signed _____ (TECHNICIAN)

DATE 4-19-89

INV. NO. 24340