

1 020380

5-12

55

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
300 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19-047-21,378-0000  
E/2 E/2 NW, SEC. 8, T. 24 S, R. 17 W/4

TECHNICIAN'S PLUGGING REPORT

3960 feet from S section line

2970 feet from E section line

Operator License # 5056

Lease Name Greene "A" Well # 1-8

Operator: F.G. Holl Company

County Edwards 146.80

Name & Address P.O. Box 780167

Well Total Depth 4517 feet

Wichita, KS 67278-0167

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8-5/8" feet 300

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sterling Drilling Company License Number 5142

Address P.O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 12 a.m. Day: 12 Months: 5 Year: 19 91

Plugging proposal received from Dick

(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1175-89'  
1st plug at 1190' with 50 sx cement, 2nd plug at 600' with 50 sx cement,  
3rd plug at 350' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2 a.m. Day: 12 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1190' with 50 sx cement,

2nd plug at 600' with 50 sx cement,

3rd plug at 350' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION  
MAY 14 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.  
(if additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

Signed Glenn R. Barlow (TECHNICIAN)

DATE 5-22-91

TRV. NO. 31867

FORM MUST BE TYPED  
COPY C-1 4/90

EFFECTIVE DATE: 5-5-91

State of Kansas 15 - 047-21,378-0000

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date May 6, 1991  
month day year

C E/2 E/2 NW Sec 8 Twp 24 S, Rg 17W East West

OPERATOR: License # 5056  
Name: F. G. HOLL COMPANY  
Address: R. O. BOX 780167  
City/State/Zip: Wichita, Kansas 67278-0167  
Contact Person: Elwyn B. Nagel  
Phone: (316) 684-8481

3960' feet from South line of Section  
2970' feet from East line of Section

(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5142  
Name: Sterling Drilling Company

County: Edwards  
Lease Name: GREENE A Well #: 1-8  
Field Name: Wayne NW

Is this a Prorated Field? yes  no   
Target formation(s): Cher. Sd. Miss. Kind. Sd.

Nearest lease or unit boundary: 330'  
Ground Surface Elevation: Est. 2115' feet MSL

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Inj  Infield  Mud Rotary  
 Gas ... Storage  Pool Ext.  Air Rotary  
... OAWO ... Disposal  Wildcat  Cable  
... Seismic; ... # of Holes

Domestic well within 330 feet: yes  no   
Municipal well within one mile: yes  no

Depth to bottom of fresh water: 160'  
Depth to bottom of usable water: 280'

Surface Pipe by Alternates: X 1 X 2  
Length of Surface Pipe Planned to be set: 300'

If OAWO: old well information as follows:  
Operator: CONSERVATION DIVISION  
Well Name: Wichita, Kansas  
Comp. Date: Old Total Depth

Length of Conductor pipe required: NA  
Projected Total Depth: 4500'

Formation at Total Depth: Viola  
Water Source for Drilling Operations: X well other

Directional, Deviated or Horizontal wellbore? yes  no   
If yes, total depth location: \_\_\_\_\_

DWR Permit #: (Applied for by Sterling Drig.)  
Will Cores Be Taken?: yes  no

If yes, proposed zones: \_\_\_\_\_

Exp. 10/30/91

AFFIDAVIT

300' Alt. I. Reg. RECEIVED  
STATE CONSERVATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101 et. seq.

It is agreed that the following minimum requirements will be met:

1. The appropriate district office shall be notified before setting surface pipe;

MAY 14 1991

CONSERVATION DIVISION  
Wichita, Kansas

Pusher Dick  
 SPUD DATE MAY 4 1991 INIT. GB  
 LENGTH SURFACE PLANNED 300' of 8 3/4"  
 RESERVE PIT STATUS- REMOVE FLUID LINED  
 after salt sect. bbls. when done bbls.  
 RATHOLED AHEAD? Y N SIZE HOLE  
 SURFACE PIPE @ CONDUCTOR  
 ANHYDRITE T-1175 B-1189 ELEVATION  
 TD 4517 FORMATION Viola  
 RAN PIPE @ SX DV TOOL SX ALT II DONE Y N  
 Arbuckle Plug @ Ft. W/ SX  
 Hug./Council @ Ft. W/ SX  
 Anhydrite Base @ 1190 Ft. W/ 50 SX  
 1/2 Base Anhy. @ 600 Ft. W/ 50 SX  
 1/2, 1/2 Plug @ Ft. W/ SX  
 Bottom Surface @ 350 Ft. W/ 40 SX  
 40' Plug @ 40 Ft. W/ 10 SX  
 RAT HOLE CIRC/W/ SX MOUSE HOLE W/ 10 SX  
 WATER WELL SX (Irr. Well Pond  
 Hauling  
 TECHNICIAN Burbu DATE 5-3-91  
 TYPE OF CEMENT 60/40 6%  
 STARTING TIME 12:02 (AM/PM) DATE 5-12-91  
 COMPLETION TIME 2:00 (AM/PM) DATE 5-12-91  
 CEMENT COMPANY B.S.

60/40 ps 670 92