

15-047-20158-0000

1031309 1-19

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-17,685

SE SE NE, SEC. 8, T. 24 S, R. 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

3080 feet from S section line

440 feet from E section line

Operator: F.G. Holl Company L.L.C.

Lease Name Nixon Well # 2-8

Name & Address P.O. Box 780167

County Edwards

Well Total Depth 2410 78.33 feet

Wichita, KS 67278-0167

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well X O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1:20 p.m. Day: 19 Month: 1 Year: 19 95

Plugging proposal received from Thom Pool

(company name) F.G. Holl Company (phone) 316-995-3171

were: 4 1/2" at 790' w/200 sx cement, PBD 790', Perfs at 657-681'
1st plug pump hulls and 25% over 4 1/2" casing volume to fill with cement,
Check annulus.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 19 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug mixed and pumped 200 lbs. hulls and 55 sx cement down

4 1/2" casing. Shut in pressure 0 psi.

2nd plug pumped 20 sx cement down 8 5/8" annulus.

Maximum pressure 0 psi and shut in 0 psi.

Cement dropped 115'. Topped off with redi-mix.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form)

INVOICED
observe this plugging.

DATE 2-3-95

INV. NO. 42142

1-19 MAR 16 1995

Signed Steve Durrant
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
JAN 2 1995
CONSERVATION DIVISION
WICHITA, KANSAS