

To: 1 090745  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-047-20,414-0000  
SW SW SE, SEC. 13, T 24 S, R 17 WEX  
330 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT 10-24  
Operator License # 5056

Lease Name Derley Well # I-13  
County Edwards 144.13  
Well Total Depth 4435 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 256

Operator: F.G. Holl Co.L.L.C.  
Name & Address  
P.O. Box 780167  
Wichita, KS 67278-0167

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWC Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:30 a.m. Day: 24 Month: 10 Year: 19 96

Plugging proposal received from Thom Pool

(company name) F.G. Holl Co. (phone) 316-793-0289

Perfs: 4 1/2" at 4435' w/150 sx cement, PBTB 4335', Perfs at 4290-92, 4308-12'

1st plug sand back to 4240' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 a.m. Day: 24 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4240' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

10-28-96

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2370' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

DATE 10-29-96

Signed [Signature]  
(TECHNICIAN)

INV. NO. 46849

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 29 1996