

1051342

8-9

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,742-0000

C NW SE, SEC. 13, T. 24 S, R. 17 W/E

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Derley Well # 2-13

Operator: F.G. Holl Company

County Edwards 144.40

Name: P.O. Box 780167

Well Total Depth 4443 feet

Address Wichita, KS 67207

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4:45 p.m. Day: 9 Month: 8 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-995-3171

were: 4 1/2" at 4438' w/225 sx cement, PBTD 4376', Perfs at 4312-16'

1st plug sand back to 4260' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:25 p.m. Day: 9 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded at 4316' with 4 sx cement on top of sand through
bailer.

8-14-90

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
released 8 5/8" wiper plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1990

Maximum pressure 550 psi and shut in 100 psi.

Witnessed by Steve Middleton.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2118' of 4 1/2" casing.
(If additional description is necessary, use **BACK** of this form.)

CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

DATE: AUG 23 1990

INV. NO. 29014

Signed Richard W. Lacy
(TECHNICIAN)