

1 090147

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,160-0000

NW SW SW, SEC. 13, T 24 S, R 17 W/X

990 feet from ~~W/S~~ section line

330 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Miller Well # 3-13

Operator: F. G. Holl

County Edwards

Name & Address 6427 East Kellogg

Well Total Depth 4495 ^{146.09} feet

Wichita, KS 67207

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Company License Number 5142

Address P. O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 12:00 am Day: 23 Month: March Year: 19 84

Plugging proposal received from Jim Shriner

(company name) Sterling (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1110' with 50 sx cement

2nd plug at 480' with 70 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plug water well with 5 sx cement

Plugging Proposal Received by R. B. Arthur
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:15 am Day: 23 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1110' with 50 sx cement, 2nd plug at 480' with

70 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rathole with 15 sx cement, plug water well

with 5 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton # 778774

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
RECEIVED
3-29-84
MAR 29 1984
CONSERVATION DIVISION
Wichita, Kansas

I (did not) observe this plugging.

Signed R. B. Arthur
(TECHNICIAN)

INVOICED
DATE 3-29-84
INV. NO. 0987