

To: 1080017 API NUMBER 15-093-21,129-0000
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION App. SW SE NE, SEC. 4, T 24 S, R 35 WXX

130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT 2-7

Operator License 5952 Lease Name Barrow Gas Unit Well 2HI

Operator: Amoco Production Company County Kearny

Name: _____ Well Total Depth 2697 87.65 feet

Address P.O. Box 800, Room 924 Conductor Pipe: Size _____ feet

Denver, CO 80201 Surface Casing: Size 8 5/8 feet 858

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Energy Services License Number _____

Address: _____

Company to plug at: Hour: 10:30 a.m. Day: 7 Month: 2 Year: 19 96

Plugging proposal received from Benny Hill

(company name) Amoco Production Co. (phone) 316-356-1237

logs: 5 1/2" at 2637' w/700 sx cement, 5 1/2" slotted pipe at 2437-2697'

1st plug pump 500 lbs. hulls and fill casing with cement.

Check backside.

2-9-96

RECEIVED
KANSAS CORP COM
1996 FEB 19 AM 10:39

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 7 Month: 2 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 500 lbs. hulls in first 10 bbl. of a total of 200 sx cement, Maximum pressure 40 psi, well on vacuum.

2nd plug pumped 60 sx cement down 8 5/8" X 5 1/2" annulus. Shut in 200 psi. Waited two hours and topped 5 1/2" with 81 sx cement.

Remarks: Used Halliburton Lite cement by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 2-20-96

Signed Kevin D. Shurt
(TECHNICIAN)

INV. NO. 44858

2-7 APR 26 1996