

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-209-19026-00-00
 Spot: SWENE SWENE Sec 32 Twp 11 S Rng 25 ☒ E / ☐ W
 2996 Feet from ☐ N / ☒ S Line of Section
 732 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 39.052289 Long: 94.651751 Date: 8/22/16 7-14-16
 Lease Name: EPPS Well #: EPP01
 County: Wyandotte Total Vertical Depth: 150 feet

Operator License No: 101
 Op Name: STATE OF KANSAS
 Address 1: 266 N. Main St. Ste. 266
 Address 2:
 City: WICHITA
 State: KS Zip Code: 67202 - 1513

Well Type: RES - Residential Gas Well UIC Docket No.: Date/Time to Plug: 7/15/16 /
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Recd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 7/15/16 / KCC Agent: Frank Guilfoyle, Tom Bilgen

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Move equipment to location. Empty out shed that was over well. Cut the posts so we could move shed from over the well. Put equipment on location. Pull 3/4" from inside 2". Run 1" and reamer inside 2" to 150 ft and hit bottom. Pull 1" and reamer. Perforate well at three intervals. Could not wash 1" down the backside of the 2" pipe. Wash inside 2" and pump Portland cement from 150 ft to surface. Pull pipe and top off well. Pump total of 14 sacks of cement. Well plugged.	75	150	TBG - Tubing	

Remarks: Contract # 38595. Control # 20170003-001. GPD'ed NAD 83 by T. H. Category I

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: ☐ Yes ☐ No

District: 03 Received KANSAS CORPORATION COMMISSION SEP 02 2016 CONSERVATION DIVISION WICHITA, KS
Frank Guilfoyle (Technician)
Tom Bilgen Form: District Plugging Report -