

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hamilton County, Sec. 31 Twp. 24S Rge. 39W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Earl F. Wakefield
Lease Name Rice Well No. 1-31
Office Address 515 Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 4 19 64
Application for plugging filed May 5 19 64
Application for plugging approved May 5 19 64
Plugging commenced May 4 19 64
Plugging completed May 4 19 64
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Verbal W. L. Nichols

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Not Productive Depth to top Bottom Total Depth of Well 2475 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	183	8 5/8"	183	None Cmt. Circ.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The hole was drilled to a total depth of 2475 feet with rotary mud having a weight of 11.0#/gal, funnel viscosity of 34 seconds and a water loss of 10.8 cc.

The Plugging was executed as follows: Hole filled with the drilling mud and three plugs were spotted through drill pipe.

Plug #1 from 540' to 400-140' -- 40 Sacks.

Plug #2 from 210' to 138-72' -- 20 Sacks.

Plug #3 -- A wooden Halliburton plug was placed at 30' and One sack of Cottenseed Hulls were placed above the plug. The casing was then filled to the surface with ten sacks of cement.

STATE CORPORATION COMMISSION

MAY 18 1964
5-18-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Earl F. Wakefield
Address 515 Union Center Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
EARL F. WAKEFIELD (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
515 Union Center Building, Wichita
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of May, 19 64

My commission expires January 25, 1965
Wanda H. Riley Notary Public.

LEASE: RICE #1-31
OWNER: EARL F. WAKEFIELD
CONTRACTOR: EARL F. WAKEFIELD
COMM: 4-30-64
COMP: 5-4-64

LOCATION: C NE SW
SECTION 31-24S-39W
HAMILTON COUNTY, KANSAS
CASING: 8 5/8" Set @ 183'
R.T.D. 2475 - - D & A

ELEVATION: 3207 K.B.

Surface Soil	25
Sand	125
Clay	160
Blue Shale	186
Shale & Shells, Red Bed	610
Red Bed, Shale W/Anhydrite	980
Shale and Red Bed	1250
Salt	1320
Salt and Shale	1598
Anhydrite	1645
Shale and Shells	1838
Anhydrite	1864
Shale and Shells	1895
Shale - Shells	2110
Shale & Shells W/Anhydrite & Sand	2240
Lime and Shale	2395
Lime	2475
R.T.D.	2475

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1964
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, Fred S. Barker, do hereby certify that the above is a true and correct copy of the log on the Rice #1-31, located in the C NE SW Section 31-24S-39W, Hamilton County, Kansas.

EARL F. WAKEFIELD

BY Fred S. Barker

Subscribed and sworn to before me this 14th day of May, 1964.

My commission expires:
January 25, 1965

Wanda W. Riley
NOTARY PUBLIC