

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 16 Twp. 30S Rge. 8W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SE NW

Lease Owner Bachus Oil Company

Lease Name Wells Well No. A-3

Office Address 721 E. Central

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed April 27 19 62

Application for plugging filed April 27 19 62

Application for plugging approved April 27 19 62

Plugging commenced April 27 19 62

Plugging completed April 27 19 62

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hampel

Producing formation None Depth to top Bottom Total Depth of Well 3200 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
0'to 60' Surface	Water	0'	60'	8 5/8	211	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole from 4200 to 200 with mud. Set plug No. 1 at 200 with 1/4 sack of hulls, 15 sacks cement through drill pipe. Fill remainder with mud to 40 ft. Set plug No. 2 at 40' with 1/4 sack hulls and 10 sacks of cement. Used 3 Sacks cement in Rat Hole.

RECEIVED
STATE CORPORATION COMMISSION
1962

CONSERVATION DIVISION
Wichita, Kansas
5-3-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bachus Oil Company

Address 721 E. Central, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Dave Bachus (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dave Bachus Dave Bachus

721 E. Central, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1962

My commission expires January 26, 1965

Nelson R. Thomas Notary Public.



WELLS A-3

Company: Bachus Oil Company
 Contractor: Bachus Oil Company

Location: SW SE NW
 Sec. 16-30S-8W
 Kingman County
 Kansas

Commenced: April 12, 1962
 Completed: April 27, 1962

Elevation: 1526 KB

Casing Record: 8 5/8" at 211'
 w/ 225 Sacks
 Cement, 2% CaCl

Production: Dry

Sand	0	40
Sand, Shale & Shells	40	226
Sand & Shale	226	250
Shale	250	815
Shale & Shells	815	1125
Lime & Shale	1125	1250
Lime	1250	1750
Lime & Shale	1750	2095
Shale & Shells	2095	2334
Shale	2334	2486
Lime & Shale	2486	3075
Lime	3075	3140
Lime & Shale	3140	3495
Lime	3495	3865
Lime & Shale	3865	3911
Lime	3911	3940
Lime & Shale	3940	4049
Lime	4049	4173
Miss. Lime & Chert	4173	4200

Total Depth 4200

Miss. 4173 (-2647)

DST #1: 4171-4200
 Open 1 hour
 Rec. 90' Mud
 FP 31-31
 BHP 408-113
 HH 2249-2241

RECEIVED
 STATE CORPORATION COMMISSION

JUN 11 1962

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Nelson R. Thomas
 Nelson R. Thomas

Subscribed and sworn to before me this 8th Day of June, 1962

My commission expires Oct. 14, 1964

Lovene C. Ehrsam
 Lovene C. Ehrsam