


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 18 Twp. 30 Rge. 18 (E) (W) x

Location as "NE/CNW/SW" or footage from lines C NW SE  
Lease Owner Sierra Petroleum Co.  
Lease Name Messenger Well No. #1  
Office Address Box 232, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 12-16-69 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 12-19-69 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4312' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	4311'	3238.70'
				8 5/8"	224'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 4200'. Mixed and ran 3 sacks cement thru dump bailer.  
Squeezed hole with 15 sacks gel and displaced with 65 sacks cement with 6% gel added.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1969  
CONSERVATION DIVISION  
Wichita, Kansas

12-23-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND sworn to before me this 22 day of December, 1969

My commission expires October 1972

Sidney S. Miller  
Notary Public.

SIERRA PETROLEUM COMPANY, INC.  
Messenger #1

C/NW SE Sec. 18-30S-8W  
Kingman County, Kansas

Total Depth: 4312'

Elev: 1576' KB

Comm: 10/13/56

Zero: 7.84

Comp: 10/29/56

Casing:

Cements:

8 5/8" @ 224'

150 sacks of Bulk

4 1/2" @ 4311'

175 sacks of Bulk

FORMATION

DEPTH

Sand & redbed	224
Shale	700
Shale & shells	1102
Anhydrite	1122
Shale & shells	1380
Lime & shale	3590
Lime	4175
Lime & chert	4240
Lime	4310

TOPS:	Anhydrite	1102
	Hebner	3281
	Douglas	3310
	Kansas City	3485
	Conglomerate	4176
	Mississippi	4215

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1969  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) sst  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Honaker

Subscribed and sworn to before me this 31st day of October, 1956.

Notary Public

My commission expires: 10-17-59