


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

County. Sec. 25 Twp. 30 Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines NE/NE/SW  
Lease Owner Purcell & Mull Drilling Co., Inc.  
Lease Name Kiger Well No. 1  
Office Address 6405 East Kellogg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed 8-29 1955  
Application for plugging filed 9-2 1955  
Application for plugging approved 9-2 1955  
Plugging commenced 9-1- 1955  
Plugging completed 9-6- 1955  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4357 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugging started 9-1-55 and completed 9-6-55. Measured in to TD 4357 and plugged off bottom with rock to 4310'. Dumped in 5 sacks of cement and shot casing off at 3505'. Pulled pipe out of hole and plugged well with heavy mud to 200'.  
10'  
Set permanent/rock bridge, and dumped in 27 sacks of cement. Filled hole with heavy mud to 25', set permanent rock bridge, and dumped in 8 sacks of cement for cap on well.


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.  
Address P. O. Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Frank H. Purcell (employee of owner) or (owner) or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of September, 19 55

January 28, 1957. Ethel Zimmerman Notary Public.



**PLUGGING**  
FILE SEC 25 T. 30 R. 8 W  
BOOK PAGE 146 LINE 43

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 17 1955  
9-17-55  
CONSERVATION DIVISION  
Wichita, Kansas

15-695-01568-0000

ROTARY DRILLERS LOG

COMPANY : Purcell-Hull Drilling Co., Inc. ROTARY DRILLING COMMENCED: 8-2-55  
 Wichita, Kansas

CONTRACTOR : Purcell-Hull Drilling Co., Inc. ROTARY DRILLING COMPLETED: 8-11-55  
 Wichita, Kansas

CASING RECORD : Set 8 5/8" Surf. Csg. @ 154' cemented with 125 sacks cement.  
 Set 5 1/2" Csg. @ 4357' cemented with 150 sacks cement.

LOCATION: KIGER #1  
 NE NE SW of Sec. 25-30S-8W  
 Kingman County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Sand	70	Lime & Shale	3422
Red Rock	154	Sand & Shale	3512
Red Bed, Shale & Shells	690	Lime & Shale	3900
Shale & Shells	1320	Lime	4050
Anhydrite, Shale & Lime	1400	Lime & Shale	4116
Lime	1600	Lime	4214
Lime & Shale	1775	Lime & Shale	4277
Lime	1880	Shale & Lime	4326
Lime & Shale	2015	Lime	4340
Shale & Lime	2885	Miss. Chat	4352
Lime & Shale	3017	Lime	4357 R.T.D.
Shale, Lime & Sand	3133		

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Purcell-Hull Drilling Co., Inc.

*Frank H. Purcell*  
 FRANK H. PURCELL, SECRETARY

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Subscribed and sworn to before me this 22nd day of August, 1955.

*Ethel Zimmerman*  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: JANUARY 28, 1957.

**PLUGGING**  
 FILE SEC 25 T 30 R 8 W  
 ROCK PAGE 146 LINE 43