

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-095-00093-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Kingman County, Sec. 25, Twp. 30S, Rge. 8W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NE SE

Lease Owner Beardmore Drilling Company

Lease Name Aldrich Well No. 2

Office Address 827 Beacon Building - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 18 19 55

Application for plugging filed March 17 19 55

Application for plugging approved March 19 19 55

Plugging commenced March 28 19 55

Plugging completed March 31 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 4384 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	128'	None
				5-1/2"	4384'	3819'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set a Lane Wells plug at 4330' and perforated casing from 4300' to 4312'. Filled the hole with sand from 4300' to 4290' and ran 6 sacks of cement. Mudded the hole to 210', set a 10' rock bridge and ran 25 sacks of cement at 200'. Mudded the hole to 18' and ran 5 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Heber Beardmore (producer of owner) and operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of April, 1955

Leonard P. Tolle

Notary Public.

My commission expires January 28, 1956

RECEIVED  
STATE CORPORATION COMMISSION

APR - 7 1955

4-7-55

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 25 Twp 30S Rge 8W  
BOOK PAGE 105 LINE 26

15-095-00093-0000

ALDRICH #2

SW NE SE, Sec. 25-30S-8W  
Kingman County, Kansas

Drilled for: Beardmore & N.C.R.A.  
Drilled by: Purcell-Mull Drilling  
Co., Inc.

Casing Record:

128' of 8-5/8" w/100 sacks  
5-1/2" 15.5# J-55 @ 4384' w/75 sacks

Drilling Commenced: 2-5-55  
Drilling Completed: 2-18-55

Elevation: DF 1582  
Gr. 1580

<u>FORMATIONS</u>	<u>DEPTH</u>
Sand	20
Red Bed	420
Shale & Shells	1200
Anhydrite & Shale	1350
Lime & Shale	1510
Lime & Shale	1645
Lime & Shale	1840
Lime & Shale	2120
Lime & Shale	2230
Lime & Shale	3120
Lime & Sand	3205
Lime & Shale	3320
Lime & Shale	3518
Lime & Shale	3620
Lime & Shale	3807
Lime & Shale	3868
Lime	3914
Lime & Shale	3957
Lime	4306
Chert & Lime	4321
Rotary Total Depth	4384

TOPS:

Mississippi 4283

PERFORATED - 4342'-4346'

LANE WELLS PLUG - 4330'

PERFORATED - 4300'-4312'

D&A

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and ability.

*Beardmore*

Subscribed and sworn to before me this 16th day of March, 1955.

*Leonard P. Tolk*  
Notary Public

My Commission Expires:  
January 28, 1956

RECEIVED  
STATE CORPORATION COMMISSION

MAR 18 1955

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 25 T 30 R 8W  
BOOK PAGE 105 LINE 25