

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

KINGMAN County, Sec. 21 Twp. 30s Rge. 8 KEY (W)  
Location as "NE/CNWKSWK" or footage from lines SW SE NE  
Lease Owner PETROLEUM, INC.  
Lease Name MESSENGER Well No. R-1  
Office Address R.R. #2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) GAS WELL  
Date well completed AUGUST 28 19 68  
Application for plugging filed SEPTEMBER 12 19 68  
Application for plugging approved SEPTEMBER 13 19 68  
Plugging commenced SEPTEMBER 18 19 68  
Plugging completed SEPTEMBER 20 19 68  
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

NORTH



Locate well correctly on above  
Section Plot

If a producing well is abandoned, date of last production NONE 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R. J. WARREN  
Producing formation MISSISSIPPI Depth to top 4187 Bottom 4246 Total Depth of Well 4246 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION   | CONTENT                | FROM  | TO    | SIZE   | PUT IN | PULLED OUT |
|-------------|------------------------|-------|-------|--------|--------|------------|
| MISSISSIPPI | SLIGHT AMOUNT OF WATER | 4198' | 4222' | 8-5/8" | 244    | NONE       |
|             |                        |       |       | 4-1/2" | 4245'  | 3787'      |
|             |                        |       |       |        |        |            |
|             |                        |       |       |        |        |            |
|             |                        |       |       |        |        |            |
|             |                        |       |       |        |        |            |
|             |                        |       |       |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MIXED AND DUMPED 5 SACKS CEMENT ON BOTTOM. HEAVY MUD TO 254', SET ROCK BRIDGE FROM 254' TO 244'. MIXED AND DUMPED 25 SACKS CEMENT FROM 244' TO 169'. MUD FROM 169' TO 40'. SET 10' ROCK BRIDGE FROM 40' TO 30'. MIXED AND DUMPED 10 SACKS CEMENT FROM 30' TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
9-27-68

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RUSS CASING PULLING, INC.  
Address BOX 1082, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
MONTE CHADD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.  
(Signature) [Signature]  
ROUTE 2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of SEPTEMBER, 19 68

[Signature] Notary Public.

My commission expires MAY 28, 1969

# WELL LOG

COMPANY Petroleum, Inc.

SEC. 21, T. 30S R. 8W

FARM Messinger

NO. R-1

LOC. SW SE NE


TOTAL DEPTH 4250'

COUNTY Kingman Co., Kansas

COMM. 8-3-68

COMP. 8-13-68

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 244' w/325. sx  
4 1/2" @ 4245' w/100. sx

ELEVATION 1533' KB

PRODUCTION Mississippi

FIGURES INDICATE BOTTOM OF FORMATIONS

- 60' Sand
- 730' Red Bed
- 755' Anhydrite
- 760' Blue Shale
- 1190' Shale
- 1825' Lime & Shale
- 2014 Lime
- 3501' Lime & Shale
- 4038' Lime
- 4140' Lime & Shale
- 4211' Lime & Chert
- 4250' Cherty Lime
- 4250' RTD

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas }  
County of Barton } SS

I, Eunice McEachern of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Messinger #R-1 well.

Eunice McEachern

Subscribed and sworn to before me this 15th day of August 1968

My Commission Expires: November 5th, 1969

Richard S. Loys  
NOTARY PUBLIC