


15-095-01566-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 21 Twp. 30S Rge. 8 (A) (W)
Location as "NE/CNW/SW" or footage from lines NW SE SW
Lease Owner National Cooperative Refinery Association
Lease Name Carrick "B" Well No. 2
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 11, 19 57
Application for plugging filed August 12, 19 57
Application for plugging approved August 14, 19 57
Plugging commenced August 11, 19 57
Plugging completed August 11, 19 57
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4370 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	262'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Mudded hole to 250'. Set plug and 1/4 sack hulls plus 20 sacks of cement. Mudded hole to 35', set plug and 1/4 sack hulls plus 10 sacks of cement, on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Virginia Drilling Company
Address Brown Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick
C. R. Sears (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)
305 Rule Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1957

My commission expires November 26, 1960.

Nell McComb Notary Public.
STATE COMMISSIONER 8-20-57

PLUGGING
FILE SEC 21 T 30 R 8W
BOOK PAGE 35 LINE 34

AUG 20 1957
CONSERVATION DIVISION
Wichita, Kansas

Well: Carrick B # 2
 Location: NW SE SW, Sec. 21-30a-8w, Kingman County, Kansas
 Company: NCRA
 Contractor: Virginia Drilling Co., Inc.
 Commenced: July 25, 1957
 Completed: August 11, 1957
 Total Depth: 4370
 Elevation: 1589 D.F.

FORMATION	DEPTH
Surface clay-sand	0-40
Redbed-shale-shells	40-262
Shale-shells	262-1080
Shale-salt	1080-1240
Shale-lime streaks	1240-1350
Sandy lime-shale	1350-1510
Lime Brk.	1510-1635
Lime-shale	1635-1790
Lime	1790-1890
Lime-shale	1890-2610
Lime	2610-2710
Lime-shale	2710-2825
Lime	2825-3295
Lime-shale	3295-3330
Shale-sand	3330-3380
Lime	3380-3460
Lime-sand	3460-3505
Lime	3505-4125
Lime-shale	4125-4165
Lime brk.	4165-4220
Lime-shale	4220-4255
Cherty lime	4255-4276
Chert-shale	4276-4280
Shale-chert	4280-4335
Lime	4335-4370

Set 262' of 8-5/8" csg.
 w/140 sks. bulk cement.

TOPS:

Heebner	3287
Toronto	3300
Douglas Sand	3321
Lansing	3505
Base K. C.	4204
Mississippi	4255

S. A. Murphy
 S. A. Murphy

Subscribed and sworn to before me this 13th day of August, 1957.

Jane M. Underwood
 Jane M. Underwood

My commission expires March 15, 1958.

RECEIVED
 STATE CORPORATION COMMISSION
 8-20-57
 AUG 20 1957

PLUGGING
 FILE SEC 21 T. 30 R. 8W
 BOOK PAGE 35 LINE 34

CONSERVATION DIVISION
 Wichita, Kansas