

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
111 No. Broadway  
Wichita, Kansas

Stafford

County. Sec. 30 Twp. 24S Rge. (E) 15 (W)

Location as "NE/CNW%SW%" or footage from lines SE NE SE

Lease Owner Humble Oil & Refining Co., Carter Division

Lease Name J. E. Seibert Well No. 1

Office Address Box 786, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 10-23 1959

Application for plugging filed 9-3 1959

Application for plugging approved 9-9 1959

Plugging commenced 12-10 1959

Plugging completed 12-18 1959

Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production 12-3 1959

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot

Producing formation Kinderhook Depth to top 4270' Bottom 4284' Total Depth of Well 4330 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kinderhook	Oil	4270'	4284'	8-5/8"	205'	0'
				4-1/2"	4348'	2301'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 4294' and found it open. Filled w/sand to 4245' and dumped 5 sacks of cement with bailer. Pulled 4 1/2" casing, cleared hole, hooked up circulating pump and squeezed well with 36 bbls of mud and 59 sacks of cement. Pumped 8-5/8" Halliburton plug between mud and cement. Left overnight. Check in and found top of cement at 20', ran 6 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

J. D. Simmons (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. D. Simmons, District Superintendent  
Box 786, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 1960

My commission expires 8-19-61

William H. Knisley - Notary Public.




WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. WILLIAM GRAHAM OIL COMPANY  
Farm. Seibert No. 1

SEC. 30 T. 24 R. 15W  
SE NE SE

Total Depth. 4330  
Comm. 9-26-56 Comp. 10-14-56  
Shot or Treated.  
Contractor. Graham-Michaelis Drlg Co.  
Issued. 11-17-56

County Stafford  
KANSAS



CASING:  
8 5/8" 203' cem w/175 sx.  
4 1/2" 4328' cem w/200 sx.

Elevation. 2048 R.B.

Production. 50 BOPD

Figures indicate Bottom of Formations

sand, gravel	145
shale blue	333
red bed, sand	715
shale	1190
anhydrite	1225
shale, shells	2050
lime-shale	3737
shale, lime	3816
lime	4061
lime, shale	4230
chert Miss.	4269
sand, shale RTD	4330
Total Depth	

Tops: Scout	
Heebner	3650
Toronto	3672
Douglas	3686
Brown lime	3791
Lansing	3799
Base Kansas City	4070
Congl.	4200
Miss.	4230
Kinderhook Shale	4261
Kinderhook sand	4263
Viola	4315