

15-075-00075-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail & Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hamilton County. Sec. 15 Twp. 24S Rge. 39W (W)

Location as "NE/CNW/SW" or footage from lines C-NW/4, SE/4, NE/4

Lease Owner Amerada Petroleum Corporation & Edwin L. Cox

Lease Name Foreman-McNeill Unit Well No. 1

Office Address Box 197, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 13, 19 58

Application for plugging filed May 19, 19 58

Application for plugging approved May 20, 19 58

Plugging commenced June 2, 19 58

Plugging completed June 4, 19 58

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives, Garden City, Kansas

Producing formation - Depth to top - Bottom - Total Depth of Well 2610 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	339'	None
				5-1/2"	2608'	1412'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Loaded Hole W/water, dumped sand in 5-1/2" Casing from 2433' to 2400' & dumped 5 Sacks Cement from 2400' to 2360' W/Bailer
Filled hole W/heavy mud from 2360' to 335', Set rock bridge from 335' to 325'
Spotted cement plug from 325' to 275' W/20 Sacks Cement
Filled Hole W/heavy mud from 275' to 35', Set Rock Bridge from 35' to 25'
Spotted Cement Plug from 25' to 0' W/10 Sacks Cement. Finished @ 11:30 AM 6-4-58

6-9-58

RECEIVED
STATE CORPORATION COMMISSION

JUN 9 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company

Address Box 304, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Ernest Higgins (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Higgins

Box 197, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of June, 1958

Charles W. Anderson

Notary Public.

My commission expires November 21, 1961

PLUGGING
FILE SEC 15 T 24 R 39W
BOOK PAGE 101 LINE 1A

June 10, 1958

TO: State of Kansas

AMERADA-COX
 FOREMAN-MCNEILL UNIT NO. 1
 C NW/SE/NE
 Sec. 15-24S-39W
 Hamilton County, Kansas

DRILLER'S LOG:

<u>From</u>	<u>To</u>	
0'	65'	Sand & Gravel
65'	207'	Black Shale
207'	300'	Blue Shale
300'	348'	Shale & Gyp
348'	450'	Shale & Pyrite
450'	535'	Shale & Gyp
535'	700'	Red Bed
700'	1179'	Red Bed & Gyp
1179'	1302'	Lime Stone & Shale
1302'	1578'	Red Bed & Shale
1578'	1925'	Red Bed & Gyp
1925'	1940'	Anhydrite
1940'	2050'	Red Shale & Lime Shells
2050'	2220'	Red Shale & Lime
2220'	2274'	Anhydrite
2274'	2386'	Red Bed & Anhydrite
2386'	2527'	Lime & Shale
2527'	2571'	Shale & Lime
2571'	2610'	Lime
	2610'	Total Depth

Well Plugging Record for the above well was forwarded to your office on June 5, 1958. Your Invoice for Plugging Service, on this well, has been received by this office and forwarded to our Tulsa Office for payment.

Amerada Petroleum Corporation
 Box 197
 Great Bend, Kansas

RECEIVED
 STATE COMMISSION

JUN 11 1958

REGISTRATION DIVISION
 Kansas

PLUGGING			
FILE	SEC. 15	T. 24	R. 39W
BOOK	PAGE 101	LINE	19