

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-093-21,110-0000

LEASE NAME Eatinger

WELL NUMBER 5-10

1980 Ft. from S Section Line

3150 Ft. from E Section Line

SEC. 10 TWP. 24 RGE. 37 XXXXX(W)

COUNTY Kearny

Date Well Completed 10/2/90

Plugging Commenced 10/4/90

Plugging Completed **

CONFIDENTIAL

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Global Natural Resources Corp.

ADDRESS P. O. Box 4682

PHONE#(713) 880-5464 OPERATORS LICENSE NO. 4328

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/4/90 (date)

by Steve @ Dodge City Office (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top _____ Bottom T.D. 5100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	1600	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

SEE BACK Set plug 3130-2709' w/100 sx 50-50 Poz w/6% gel

Set plug 1640-1440' w/50 sx 50-50 Poz w/6% gel

SEE BACK Set plug 1020-820' w/50 sx 50-50 Poz w/6% gel

Set plug 510-310' w/50 sx 50-50 Poz w/6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____

Address P. O. Box 1598, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Global Natural Resources Corp.

STATE OF Texas COUNTY OF Harris, ss.

Melynda K. Mosley of Global Natural Resources Corp. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct.


STATE CORPORATION COMMISSION

(Signature) Melynda K. Mosley

DEC 5 1990 (Address) P. O. Box 4682, Houston, TX 77210

SUBSCRIBED AND CONSENTED TO me this 20th day of November, 1990

Wichita, Kansas



My Commission Expires: _____

Notary Public

NOTE:

Did not completely finishing plugging this well. Received a 90 day extension from the Dodge City office to wait until 1st week of January 1991 to finish plugging this well. May want to convert to a SWD.

1991