

STATE OF KANSAS
STATE CORPORATION COMMISSION
301 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

15-185-22951-0000

API NUMBER Comp. 1994

LEASE NAME Hyter

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

EASE OPERATOR National Petroleum Reserves, Inc.

SEC. 30 TWP. 24S RGE. 14W (E) or (W)

ADDRESS 260 N. Rock Rd, Suite 130, Wichita, Kansas 67206-2241

COUNTY Stafford

PHONE # (316) 681-3515 OPERATORS LICENSE NO. 9482

Date Well Completed

Character of Well Oil

Plugging Commenced 7-27-99

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-13-99

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	315'	None
				5-1/2"	4530'	2000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 4320' and 5 sks. cement. Shot pipe @2500', 2300' and 2000'. Plugged surface with 300# hulls, 10 sks. gel, 50 sks. cement, 10 sks. gel, 100# hulls, wiper plug and 175 sks. cement, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: National Petroleum Reserves, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1999
Irene Herzberg
Notary Public

AUG 20 1999
8-20-99
CONSERVATION DIVISION
Wichita, Kansas
My Commission Expires:

IRENE HERZBERG
State of Kansas
My Appt. Exp. Aug. 24, 2001

Form 07
Revised 05-