

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-185-22926-0000

LEASE NAME Hyter

WELL NUMBER 2

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 30 TWP. 24S RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed         

Plugging Commenced 07-23-96

Plugging Completed 09-06-96

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR National Petroleum Reserves, Inc.

ADDRESS 250 N. Rock Rd, Suite 130 Wichita, KS 67206

PHONE# (316) 681-3515 OPERATORS LICENSE NO. 9482

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	305'	none
				5 1/2	4429'	2418'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from          feet to          feet each s  
Plugged off bottom with sand to 4270' and 5 sks cement. Shot well @ 2612, 2418. Came loose at 2418'. Pulled pipe out of the hole. Plugged well with 300# hulls, 10 sks gel, 50 sks cement, 10 sks gel, 200# hulls. Release 8 5/8 plug, followed by 125 sks cement. Shut in. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: National Petroleum Reserves, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

9-13-96

RECEIVED  
 STATE CORPORATION COMMISSION AND SWORN TO before me this 12th day of September, 19 96

SEP 13 1996

My Commission Expires:         

CONSUMER PROTECTION DIVISION  
 WICHITA, KANSAS

