

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20740-0000

LEASE NAME DYKES

WELL NUMBER SWD NO. 1

SPOT LOCATION 600' FEL, 330' FSL, NE/4
SEC. 30 TWP. 24 S. RGE. 14 E. (W)

COUNTY STAFFORD

Date Well Completed 6/12/77

Plugging Commenced 5/29/84

Plugging Completed 5/29/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CHAPMAN EXPLORATION, INC.

ADDRESS 404 Cities Service Building
Tulsa, Oklahoma 74119

PHONE (918) 582-2247 OPERATORS LICENSE NO. 6939

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Stafford

Is ACO-1 filed? _____ If not, is well log attached? Sent with CP-1

Producing formation SWD Depth to top 510' bottom 758' T.D. 960'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Shallow Sand	Salt Water	510'	758'	8-5/8"	273	None
				5-1/2"	959	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. NOTE: The 8-5/8" was cemented to the surface and the 5-1/2" was cemented to the surface when well was originally drilled. Well was plugged as follows: Mixed 25 sacks 60/40 poz, 3% CC, 2% gel, and 100 sacks 60/40 poz, 3% CC, 2% gel, with 3 sacks hulls and pumped down 5-1/2". Shut in with 150 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SUN CEMENTERS License No. _____
Address Great Bend, Kansas

RECEIVED
STATE CORPORATION COMMISSION

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

VIRGIL L. JOHNSON (employee of operator) ~~xxx~~
~~xxxxxx~~ of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 404 Cities Service Bldg.
Tulsa, Oklahoma 74119

SUBSCRIBED AND SWORN TO before me this 6th day of June, 1984

[Signature]
Notary Public

My Commission expires: JUNE 7, 1984