

15-095-19156-0000

Form CP-3
Rev. 6-26-62

14

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1964
12-17-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: Box 308, Great Bend, Kansas

Lease Name Richardson "A" Well No. # 1

Location App. C NW NE Sec. 19 Twp. 30 Rge. 8 (E) (W) W

County Kingman Total Depth 4270

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 2:15PM Day 15th Month Dec. Year 1964

The Above well was plugged as follows:

411' of 8 5/8" surface pipe, cement circulated with 325 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 300', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICE

DATE 12/17/64

INV. NO. 358-W

Signed: Archie Elving
Well Plugging Supervisor