

~~NO~~ KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1964
3-26-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Socony Mobil Oil Co., Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name Messenger Wells Unit Well No. # 1

Location SE SE SE Sec. 17 Twp. 30 Rge. 8 (E) (W) W

County Kingman Total Depth 4333

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 5:00PM Day 24th Month March Year 1964

The Above well was plugged as follows:

310' of 8 5/8" surface pipe, cemented with 250 sacks. 4332' of 5 1/2"
long string, cemented with 200 sacks. Plug back to 4296'. Top per-
feration 4244'. Bottom of hole was sanded to 4230', and cemented
with 5 sacks. Hole was filled with mud to 330', with 10' rock bridge,
and cemented with 30 sacks, bringing the top of the cement to 237'
in the surface pipe. Hole was filled with mud to 40', with 10' rock
bridge, and cemented with 10 sacks to base of the cellar.
3125' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/26/64
INV. NO. 8849-W

Signed: Archie Elving
Well Plugging Supervisor