

15-095-00620-0000

Form CP-3
Rev. 6-9-67

KANSAS

AP
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1967
8-4-67

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name N. C. R. A.

Complete Address P. O. Box 6, Great Bend, Kansas 67530

Lease Name Carrick "C" Well No. # 1

Location SW NE NW Sec. 21 Twp. 30 Rge. 8 (E) (W)W

County Kingman Total Depth 4355'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Comstock Pipe Pulling, Inc.

Address Stafford, Kansas License No. 490

Operation Completed: Hour 2:00 P.M. Day 3rd Month August Year 1967

The above well was plugged as follows:

266' of 8 5/8" surface pipe, cemented with 150 sacks. 4350' of 5 1/2" long
string, cemented with 50 sacks. Plug back T.D. 4294'. Top perforation 4258'.
Bottom of the hole was sanded to 4175', and cemented with 10 sacks, through
the dump bailer, with cement from 4175' to 4100'. 2800' of 5 1/2" long string
was recovered from the hole. Fluid level in the hole was at 245', bridge
plug and rock bridge from 245' to 235', and cemented with 25 sacks, with
cement from 235' to 160'. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks from 30' to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 8/4/67
INV. NO. 6080-W