

KANSAS

RP

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

JAN 2 1968

Recd 1-2-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued December 1, 1967.

Operator's Full Name Champlin Petroleum Company

Complete Address: P. O. Box 308, Ellinwood, Kansas 67526

Lease Name Tjaden Well No. # 1

Location C NW NE Sec. 21 Twp. 30 Rge. 8 (E) (W) W

County Kingman Total Depth 4318'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas 67104 License No. 583

Operation Completed: Hour 1:00PM Day 30th Month December Year 1967

The Above well was plugged as follows:

269' of 8 5/8" surface pipe, cemented with 200 sacks. 4318' of 5 1/2" long string,
cemented with 100 sacks. Plug back T.D. 4282'. Top perforation 4229'. Bottom of
the hole was sanded to 4200', and cemented with 5 sacks, through the dump bailer,
with cement from 4200' to 4160'. 3420' of 5 1/2" long string was recovered from the
hole. Hole was filled with mud to 260', rock bridge from 260' to 250', and cemented
with 25 sacks, with cement from 250' to 175'. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to
the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Archie Elving*
Well Plugging Supervisor

INVOICED

DATE 1-2-68

INV. NO. 7019-W