

15-095-30258-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

SEP 24 1965
9-24-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 352 North Broadway, Wichita, Kansas

Lease Name Richardson Unit Well No. # 1

Location App. NE SE NW Sec. 30 Twp. 30 Rge. 8 (E) (W) W

County Kingman Total Depth 4405'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No.

Operation Completed: Hour 9:30AM Day 22nd Month Sept. Year 1965

The Above well was plugged as follows:

236' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 225', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 225', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/27/65
INV. NO. 1860-u