

15-009-06625-0000

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION near SE-SE

SEC. 17 TWP. 16 RGE. 11-w

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Oeser

Operator G.M. & R. Oil Co Address# 1005 E. 2<sup>nd</sup> St Wichita-Kans.

Field \_\_\_\_\_ County Barton

Total Depth 3764 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 3/4 - 160 ft Circulated with cement.  
5/8" casing set at 3650 ft. 85 sacks of cement  
cement Plug at 1450 ft. sand & chat to 1900 ft.  
blushed 5 sacks of cement at 1900 ft. Shot off  
& pulled the 5/8" casing - mud to 300 ft.  
Set rock bridge & 10 sacks of cement at 300 ft.  
Mud to 35 ft. Plug & 10 sacks of cement  
at the surface*

**PLUGGING**  
FILE SEC 17 T 16 R 11 W 1  
BOOK PAGE 42 LINE 17

**RECEIVED**  
STATE CORPORATION COMMISSION  
SEP 30 1952  
9-30-52  
CONSERVATION DIVISION  
Wichita, Kansas

C. D. Stough  
District Conservation Agent  
Date 9-18-52