

15-009-07122-0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1967
12-11-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Meltzer Oil Company

Complete Address: Drawer "B", Great Bend, Kansas 67530

Lease Name Oeser Well No. # 4

Location C NL NW NW Sec. 17 Twp. 16 Rge. 11 (E) (W) W

County Barton Total Depth 3303

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 504, Chase, Kansas License No. 436

Operation Completed: Hour 11 AM Day 6 Month 12 Year 1967

The Above well was plugged as follows:

8 5/8" 340' Cwc.

Sanded hole back to 3270' & dumped 4 sax cement with dump bailer. Pulled pipe.

Mudded hole to 320', set 10' rock bridge, & displaced 25 sax cement. Mudd to 40',

set rock bridge, & displaced 10 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/12/67
INV. NO. 6890-u

Signed: Don Truman
Well Plugging Supervisor