

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 93-30

LOCATION SW-21W-21W

SEC. 17 TWP. 16 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Osler

Operator Shell Oil Co Address Box #744 At Baud-Kans.

Field _____ County Barton

Total Depth 3306 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2" - 331 ft - Circulated with cement
 4 1/2" casing set at 3224 ft - 100 sacks cement
 3 1/2" casing at 3228 ft - 25 sacks of cement - Plugged
 back to 3000 ft with sand - Pumped 25 sacks of cement
 at 3000 ft - Shot off 2" pulled to 3 1/2" & 4 1/2" casing -
 mud to 300 ft. Set cork bridge & 10 sacks of cement
 at 300 ft. mud to 35 ft. Plus 10 sacks cement at the surface
 Foerster Casing Pulling Co. - Plugging Contractors*

PLUGGING
 FILE SEC. 17 T. 16 R. 11W
 BOOK PAGE 21 LINE 30

RECEIVED
 CORPORATION COMMISSION
 MAY 19 1953
 5-19-53
 CONSERVATION DIVISION
 Wichita, Kansas

C. H. Stough
 District Conservation Agent
 Date 5-16-53