

[Handwritten Signature]
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Lee Fisk Oil Operations

Complete Address Box 581 Russell, Kansas 67665

Lease Name George Maier Well No. 2

Location C SW SW Sec. 10 Twp. 15 Rge. (E) (W) 14

County Russell Total Depth 3236'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor SW Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 4 P Day 10 Month 12 Year 1974

The above well was plugged as follows:

- Total depth 3236' 10 3/4 csg set at 780' cwc 300 sk.
- 7" csg set at 3227' cw 500 sk cem. Perf. (2350')
- Set 7" wood plug at 2115' -poured 20' sd -dumped 5 sk cem W/dump bailer. (2115-2065)
- Cutoff & recovered 1220' of 7" csg.
- Filled 10 3/4 csg with mud to 415' -set rock & sand bridge (415-400)
- Filled with readymix cement from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 12/16/74
INV. NO. 473-6